

REDACTED

Rocky Mountain Power

Docket No. 17-035-40

Witness: Rick A. Vail

BEFORE THE PUBLIC SERVICE COMMISSION
OF THE STATE OF UTAH

ROCKY MOUNTAIN POWER

REDACTED

Supplemental Direct and Rebuttal Testimony of Rick A. Vail

January 2018

1 **Q. Are you the same Rick A. Vail who previously provided direct testimony in this**
2 **case on behalf of Rocky Mountain Power (“Company”), a division of PacifiCorp?**

3 A. Yes.

4 **PURPOSE AND SUMMARY OF TESTIMONY**

5 **Q. What is the purpose of your supplemental direct and rebuttal testimony?**

6 A. Based on the results of the 2017R Request for Proposals (“RFP”), in my supplemental
7 direct testimony, I update the status of the Aeolus-to-Bridger/Anticline Line¹ and
8 network upgrades (“Transmission Projects”) that support the Company’s decision to
9 construct or procure four new wind resources (“Wind Projects”) (collectively, the
10 “Combined Projects”). I explain the important progress the Company has made on the
11 Transmission Projects, as well as their decreasing risk.

12 In my rebuttal testimony, I respond to the direct testimony of Utah Division of
13 Public Utilities (“DPU”) witnesses Mr. Robert A. Davis and Mr. Daniel Peaco, Office
14 of Consumer Services (“OCS”) witness Mr. Philip Hayet, and Utah Association of
15 Energy Users and Utah Industrial Energy Consumers witness Mr. Bradley G. Mullins.

16 **Q. Please summarize your testimony.**

17 A. I address the following key issues for the Transmission Projects:

- 18 • An update on the status of:
- 19 • Expected design and cost;
- 20 • Engineering, Procurement, and Construction (“EPC”) contracts;
- 21 • Required permits at the federal, state, and local level; and
- 22 • The required power system analyses and easements.

¹ As defined in my direct testimony at page 2, lines 29-37.

- 23 • The necessity of these projects to reduce line losses and derates along with
24 dispatching of Company-owned resources.
- 25 • Technical analysis demonstrating that the Company’s Aeolus-to-
26 Bridger/Anticline Line will enable interconnection of up to 1,270 MW of
27 additional resources and increase transfer capability by 750 MW from east to
28 west across Wyoming.
- 29 • Mitigation of risks to minimize costs and project delays due to:
- 30 • The permitting process and the Company’s plan for obtaining required
31 permits before construction;
- 32 • Obtaining the required easements; and
- 33 • Construction delays (EPC contracts and mitigation for meeting construction
34 deadlines).
- 35 • Relevant Open Access Transmission Tariff (“OATT”) and Federal Energy
36 Regulatory Commission (“FERC”) precedent confirming the reasonableness of
37 the Company’s assumptions regarding revenues from third-party customers.
- 38 • The Company’s need for timely resource approval to maintain project
39 timelines.

40 **SUPPLEMENTAL DIRECT TESTIMONY**

41 **UPDATE ON THE TRANSMISSION PROJECTS**

- 42 **Q. Since the initial filing, has the Company maintained the project schedule and cost**
43 **estimates for the Aeolus-to-Bridger/Anticline Line?**
- 44 A. Yes. The Company has made significant progress and is on track to meet its
45 development schedule at or below the costs estimated in its direct filing.

46 **Q. Did the results of the 2017R RFP affect the costs or design of the Aeolus-to-**
47 **Bridger/Anticline Line?**

48 A. No. The results of the 2017R RFP did not affect the estimated costs or the design of the
49 Aeolus-to-Bridger/Anticline Line. As discussed below, the Company's continued
50 project development efforts have confirmed the cost estimates included in the initial
51 filing.

52 **Q. Have the network upgrades described in your direct testimony changed because**
53 **of the final shortlist Wind Projects from the 2017R RFP?**

54 A. Yes. There are changes to the network upgrades resulting from the Wind Projects
55 chosen for the final shortlist for the 2017R RFP. The Wind Projects are four facilities
56 in Wyoming totaling approximately 1,170 MW—McFadden Ridge II, TB Flats I and
57 II, Cedar Springs, and Uinta.

58 **Q. Please describe the updated network upgrades required to interconnect the Wind**
59 **Projects.**

60 A. The 230 kV network upgrades for the McFadden Ridge II and TB Flats I and II projects
61 that were identified in my direct testimony are still necessary to interconnect these
62 Wind Projects because they were selected for the 2017R RFP final shortlist.² In
63 addition, the McFadden Ridge II project will require a new three-breaker 230 kV point-
64 of-interconnection ring-bus substation on the High Plains-to-Foote Creek 230 kV line,
65 roughly two miles southwest of High Plains substation, as shown in Exhibit

² Details regarding these network upgrades can be found in my direct testimony and exhibits (page 2, lines 38-48). The Ekola project that was also included as a benchmark resource in the initial filing did not require network upgrades to interconnect, and therefore all network upgrades discussed in my direct testimony were related to the McFadden Ridge II and TB Flats I and II projects.

66 RMP___(RAV-1SD). There are also additional network upgrades required for the other
67 projects that were selected through the 2017R RFP.

68 To interconnect the Cedar Springs project, the Company must install two 230
69 kV (3000 ampere) breakers and two line positions with associated switches at the
70 Windstar substation. The Company must also install high-speed relaying to switch off
71 the shunt capacitor banks at the Riverton 230 kV bus, which are required for high-
72 voltage conditions, and rebuild approximately 56 miles of the Dave Johnston-Amasa-
73 Difficulty-Shirley Basin 230-kV line with 2-1272 bundled conductor.

74 To interconnect the Uinta project, the Company must construct a new three-
75 breaker 138 kV point-of-interconnection ring-bus substation southwest of the Whitney
76 Canyon Tap (near structure 116), with associated switches and line terminations. The
77 Company must also reconductor approximately 13.7 miles of the Q0715 - Railroad 138
78 kV line with 1-1272 ACSR/phase (line has 1-795 ACSR/phase), and modify the
79 existing Naughton remedial action scheme (“RAS”) to allow redundant communication
80 to the project.

81 RMP___(RAV-1SD) details the specifics of these additional network upgrades.

82 **Q. What are the updated costs for the network upgrades?**

83 A. Confidential Table 1 summarizes the updated costs for the network upgrades:

Confidential Table 1

Network Upgrades	
ITEM	VALUE
Transmission Line	\$ [REDACTED]
Substation	\$ [REDACTED]
Engineering	\$ [REDACTED]
Right-of-Way Acquisition	\$ [REDACTED]
PM/Environmental/Support	\$ [REDACTED]
Indirects	\$ [REDACTED]
TOTAL	\$ [REDACTED]

85 **Q. Have these costs been included in the updated economic analysis included in Mr.**
86 **Link's testimony?**

87 A. Yes.

88 **Q. Why did the network upgrade costs increase by approximately [REDACTED] million**
89 **compared to the Company's initial estimate?**

90 A. The selection of the Cedar Springs and Uinta projects to the 2017R RFP shortlist
91 required additional network upgrade costs that were not included in the original
92 estimate. Notably, however, although the network upgrade costs increased relative to
93 the initial filing, the overall costs of the Combined Projects remains roughly unchanged
94 even though customers are now receiving substantially more capacity for the same
95 overall project cost of approximately \$2 billion, as discussed further by Mr. Link in his
96 supplemental direct testimony.

97 **Q. Will these additional network upgrades delay the completion of the Transmission**
98 **Projects?**

99 A. No. The types of additional upgrades needed are fairly routine projects that the
100 Company performs in the ordinary course of business, and they can be completed well

101 before the end of 2020.

102 **Q. Have you included the information required by Utah Admin. Code R746-440-1(1)**
103 **for the new facilities described above.**

104 A. Yes. Exhibit RMP___(RAV-1SD) includes the additional relevant information required
105 for approval of a voluntary resource decision.

106 **Q. Please provide a status update on the design of the Transmission Projects.**

107 A. Currently, both the Aeolus-to-Bridger/Anticline Line and the 230 kV network upgrades
108 are in the detail design phase. For the 500 kV facilities, the major effort is focused on
109 two key elements: (1) micro-siting structures; and (2) structure design.

110 Micro-siting structures involves confirming the precise structure locations and
111 associated access roads to accommodate features such as pipelines, fiber-optic cables,
112 and other utilities, along with micro-siting to avoid sensitive biological or cultural
113 features.

114 The structure-design process focuses on selecting the tower and foundation
115 design that will be used. Before filing the initial request, the Company decided it could
116 use a new tower design that would significantly reduce the structures' weight, and
117 therefore cost, as compared to the tower design used in other segments of the Energy
118 Gateway project. The Company is in the process of developing and testing the revised
119 structures and expects to complete this by summer 2018, in line with the overall EPC
120 schedule. The Company is currently completing the initial design phase, the first
121 prototype has begun the fabrication process, and tower testing is scheduled to begin
122 mid-first-quarter 2018. Development efforts to date have confirmed the baseline
123 assumptions included in the design and cost basis of the initial filing.

124 In addition, the Company completed a geotechnical program during summer
125 2017 to further aid the EPC contractors in bid preparation and reduce the risk
126 assumptions associated with the foundation design. The overall 500 kV transmission
127 design package is on track to be complete by April 2018.

128 **Q. What is the status of the 500 kV substation design work?**

129 A. The 500 kV substation design work is on schedule. The Company has focused recent
130 efforts on thoroughly analyzing the precise location and space requirements for each
131 new substation. This has led to a reduction in the initial space requirements and allowed
132 for a balanced cut-and-fill design to reduce the cost of importing high-cost fill
133 materials. At the Jim Bridger substation, design optimization efforts will facilitate
134 construction of the new line-termination bay while minimizing disruptions to the
135 existing facility. The substation design necessary for competitive market EPC bidding
136 is anticipated to be completed by April 2018.

137 **Q. What is the status of the network upgrade facilities?**

138 A. Design work for the 230 kV network upgrades is also ongoing. The Company has
139 selected the proposed line route, after considering field surveys for biological and
140 cultural constraints, as well as incorporating landowner comments. Exhibit
141 RMP___(RAV-2SD) contains topographical maps for the proposed line route. Structure
142 design will be based upon the Company's standard design steel H frames. The
143 Company will begin design work for the 230 kV substations in early 2018. All design
144 work for the network upgrade facilities will be completed by fall 2018, to allow for the
145 competitive market procurement process to support a 2019 construction period.

146 **Q. What is the current status of the EPC contract for the Aeolus-to-Bridger/Anticline**
147 **Line?**

148 A. The Company is currently in a competitive selection process for an EPC contractor for
149 the Aeolus-to-Bridger/Anticline Line. Because the line is approximately 85 percent of
150 the total costs of the Transmission Projects, the selection of the EPC contractor will be
151 a significant milestone in confirming final project costs. The preliminary results of this
152 process have confirmed the project cost estimates included in the initial filing.

153 **Q. Please provide more detail on the status of the EPC contracts for the Transmission**
154 **Projects.**

155 A. The Company has engaged with eight transmission line contractors to secure Master
156 Service Agreement Terms and Conditions that will apply to the Transmission Projects.
157 The contractors represent some of the leading engineering and construction companies
158 in the country. Negotiations are currently ongoing to finalize these terms and conditions
159 in January 2018.

160 Concurrent with these activities, the Company issued a request for detailed
161 technical information to the same contractors. This request requires contractors to
162 provide detailed project plans, resource profiles, schedules and cost data. The responses
163 will be analyzed to develop a shortlist of contractors, based on a combination of cost
164 and viability of the overall project approach, for a final pricing event in the summer
165 2018. Contractor responses were received December 11, 2017. The data within the
166 responses will also be used to inform the analysis being performed for the Wyoming
167 Industrial Siting Permit application. The EPC contracts for the Aeolus-to-
168 Bridger/Anticline Line remain on track to be in place by October 2018.

169 For the 500/345-kV substation scope of work, the Company is currently
170 preparing a terms-and-conditions RFP that will be issued by early February 2018 to up
171 to six qualified contractors who will be responsible for full EPC services for the
172 500/345-kV substations. This RFP will also request budgetary price information. The
173 Company intends to negotiate EPC contract terms and conditions before final pricing
174 to expedite final contract negotiations in fall 2018. A final price bid event will be issued
175 to all six companies in the summer of 2018.

176 For the network upgrades, the Company intends to competitively source both
177 the transmission line and substation construction via existing term “Line Service
178 Agreements” the Company holds with over one dozen qualified contractors capable of
179 working in Wyoming. The Company may acquire major substation equipment as a
180 direct purchase through a competitive RFP to qualified vendors. The network upgrade
181 work is on schedule to be procured in late 2018 with main construction anticipated
182 during 2019.

183 **Q. What is the status of the permits required for construction of the Transmission**
184 **Projects?**

185 A. The Company has been working with various agencies and stakeholders to obtain the
186 final permits necessary to construct the facilities and the Company’s permitting
187 activities remain on schedule. A summary of key items is presented below:

188 **Section 106 Consultation, National Historic Preservation Act:** Field surveys
189 were completed during the summer of 2017. The final class III cultural report was
190 submitted to the Bureau of Land Management (“BLM”) on December 15, 2017.
191 Programmatic Amendment Agreement has been signed and approved by the Bureau of

192 Land Management and the State Historical Preservation Office. The Umbrella Historic
193 Properties Treatment Plan (which includes all Energy Gateway West in Wyoming) has
194 all of the approvals required and the project specific Historic Properties Treatment Plan
195 will be developed and submitted after acceptance of the Class III cultural report,
196 expected February 2018. Final approval by the Wyoming State Historic Preservation
197 Office of the Historic Properties Treatment Plan is expected by mid-August 2018.

198 **Plan of Development:** Work continues in close cooperation with the BLM.
199 Initial updated draft sections have been provided to the BLM, with comments received.
200 The Plan of Development is on schedule to be completed by May 2018 to support the
201 EPC procurement schedule. Final Plan of Development mapping will be completed by
202 the end of 2018 after including updated data from the 2018 field survey season.

203 **Clean Water Act Sections 401:** Wyoming Department of Environmental
204 Quality (“WYDEQ”) Water Quality Division (“WQD”) has categorically-certified the
205 majority of the 2017 USACE Nationwide Permits on non-Class 1 waters in Wyoming
206 with the expectation that applicants must comply with the permit’s terms and
207 conditions, including permit specific 401 Certification conditions for the certification
208 to be valid. These categorically-certified permits do not require an individual 401
209 Certification by the WYDEQ/WQD. The Transmission Projects require that a section
210 404, nationwide permit 12 be obtained. This will meet the requirements under the State
211 of Wyoming for Section 401 certification.

212 **Section 404/NWP 12:** The Transmission Projects have completed all wetland
213 delineations to determine impacts. These potential impacts are being reviewed for
214 avoidance via detail design reviews. The Company will submit its pre-construction

215 notification to certify the project does not exceed greater than 0.1 acre of permanent
216 impact at any one delineated wetland area. This is on schedule for approval in May
217 2018.

218 **Wyoming Industrial Siting Permit:** The Company held an initial meeting with
219 the WYDEQ with respect to the Wyoming Industrial Siting Permit and the WYDEQ
220 determined the jurisdictional determination first recorded in 2012 is still valid. The
221 Company is preparing an application for submission by the end of June 2018. The 135
222 day review period as described in the Wyoming Administrative Rules, Chapter 35, will
223 therefore conclude with a decision due by mid-November 2018.

224 **Carbon County Conditional Use Permit (“CUP”):** The Company held a
225 preliminary meeting with Carbon County to discuss the requirements of the CUP
226 application. The Company is preparing the application for a May 2018 submission with
227 an August 2018 decision.

228 **Q. What is the status of the technical studies that are necessary to support the**
229 **Transmission Projects?**

230 A. The Company performed numerous technical studies that show the benefits and
231 reliability improvements resulting from the Transmission Projects. As with any large-
232 scale transmission project, the Company continues to perform additional technical
233 studies. Confidential Exhibit RMP____(RAV-3SD) provides a detailed outline of the
234 studies performed so far and a description of the additional studies that will be
235 performed, along with the timing of the additional studies.

236 In October 2017, the Company completed detailed studies, including power
237 flow and stability analysis, evaluating a wide range of operating conditions. This study,

238 the Preliminary Aeolus West Transmission Path Transfer Capability Assessment
239 (“Preliminary Study Report”), is attached to this testimony as Exhibit RMP___(RAV-
240 4SD).

241 Preliminary North American Electric Reliability Corporation (“NERC”) FAC-
242 013-2 Transmission Assessment studies are currently underway for the Aeolus-to-
243 Bridger/Anticline line and are expected to be finalized in 2020. The first set of studies
244 to be included in this process has already been completed and showed an increase of
245 transfer capability of 750 MW from east to west across Wyoming. Technical analysis
246 shows the Aeolus-to-Bridger/Anticline line increases the system’s stiffness factor
247 sufficiently to enable interconnection of up to 1,270 MW of additional resources. All
248 of the technical study work completed to date continues to support the initial
249 assumptions for the Transmission Projects, the facilities identified, and the benefits that
250 the Transmission Projects will provide.

251 **Q. What is the status of the Company’s acquisition of rights-of-way necessary for the**
252 **Transmission Projects?**

253 A. The Company has contacted all landowners where easements for access or transmission
254 rights-of-way (or both) are required. To date, 24 offers of options for rights-of-way
255 have been issued to landowners. Four landowners have accepted and three additional
256 landowners have provided counteroffers. All remaining offers for the 500 kV project
257 will be issued by January 31, 2018. The acquisition of rights-of-way remains on track
258 to support the planned construction start date of April 1, 2019.

259 **REBUTTAL TESTIMONY**

260 **NECESSITY OF THE TRANSMISSION PROJECTS**

261 **Q. Mr. Davis has concluded that if the Wind Projects are not approved, there is no**
262 **need for the Transmission Projects. (Davis Direct, lines 36-39.) Do you agree?**

263 A. No. There is an independent need for the Aeolus-to-Bridger/Anticline Line even if the
264 new Wind Projects are not constructed because it will improve system performance and
265 reliability and directly serve customers. To be clear, even if the Wind Projects are not
266 approved, the Company’s—and the region’s—long-term transmission plans still call
267 for the construction of the Aeolus-to-Bridger/Anticline Line (and some of the network
268 upgrades) by 2024. Thus, the Company will need to construct this transmission line in
269 the near future. The question is whether it is built in 2020 when PTC-eligible wind can
270 offset the costs and produce net benefits for customer, or in 2024 at full cost to
271 customers.

272 **Q. Does Mr. Davis agree that the Transmission Projects are necessary if the Wind**
273 **Projects are approved?**

274 A. Yes. (Davis Direct, lines 306–308.)

275 **Q. What is the current status of the Company’s eastern Wyoming transmission**
276 **system?**

277 A. The Company’s eastern Wyoming transmission system is severely restrained and
278 experiences voltage-support issues. While the Company is in compliance with all
279 NERC and Western Electricity Coordinating Council (“WECC”) reliability standards,
280 the stiffness factor (measurement of a transmission system’s ability to control voltage
281 within acceptable limits) in eastern Wyoming is such that new resources cannot be

282 connected to the system, increasing the risk of voltage swings outside acceptable limits
283 in an outage condition. This system condition also limits the ability to schedule outages
284 for segments of the transmission system to perform routine maintenance.

285 **Q. Do these general conditions apply specifically in the area where the Transmission**
286 **Projects will be constructed?**

287 A. Yes. The same constraints and stiffness-factor limits present in eastern Wyoming
288 generally are present along the TOT 4A transmission path where the Transmission
289 Projects will be constructed. Because of the constraints and the stiffness-factor limit,
290 new resources cannot be connected behind the path (*i.e.*, east of the path). Further, an
291 outage of a TOT 4A transmission element results in a path derate to prevent a thermal
292 or voltage system violation and maintain system reliability. Existing generation must
293 often be curtailed to operate within derated path limits, which is a curtailment in firm
294 transmission rights used to serve customer load.

295 **Q. Mr. Davis discusses guidelines provided by the U.S. Department of Energy**
296 **(“USDOE”) related to transmission planning and construction that informed**
297 **DPU’s analysis of the Transmission Projects. (Davis Direct, lines 153–159.) What**
298 **are the guidelines identified by Mr. Davis?**

299 A. Mr. Davis identified three guidelines. The Company must: demonstrate a need for the
300 Transmission Projects; determine who pays for the Transmission Projects; and site and
301 permit the Transmission Projects.

302 **Q. What did DPU conclude based on the application of the USDOE transmission**
303 **planning guidelines?**

304 A. According to Mr. Davis, DPU concluded that the “Company planned the transmission

305 projects . . . for reliability and resiliency to support the new wind generation” and that
306 “with the new wind generation, the proposal fits [USDOE’s] guidelines.” (Davis Direct,
307 lines 170–173.)

308 **Q. Do you agree with Mr. Davis’ conclusion?**

309 A. Yes, but not his rationale. As noted above, there is a need for the Transmission Projects,
310 with or without the Wind Projects.

311 **Q. Mr. Davis also testifies that even with the Transmission Projects, the Company’s**
312 **Wyoming transmission system will still be constrained. (Davis Direct, lines 199–**
313 **202.) Do you agree?**

314 A. Yes. The Company has never indicated that the Transmission Projects alone will resolve
315 all the existing congestion in Wyoming. But the construction of the Transmission
316 Projects will relieve existing congestion and allow greater grid flexibility in eastern
317 Wyoming, and achieve these benefits with limited rate impact because of the PTCs
318 generated by the Wind Projects.

319 **Q. Mr. Mullins claims the Aeolus-to-Bridger/Anticline line may not be the best**
320 **solution for addressing transmission needs in the West. (Mullins Direct, page 21,**
321 **lines 6–7.) How do you respond?**

322 A. Mr. Mullins provides no substantive analytic support for his contention. Instead, Mr.
323 Mullins implies the Aeolus-to-Bridger/Anticline Line was developed outside of the
324 intra-regional transmission planning process required by FERC’s Order No. 1000, but
325 this implication is wrong. Contrary to this implication, the Aeolus-to-Bridger/Anticline
326 Line is an integral component of the intra-regional transmission plan developed by the
327 Northern Tier Transmission Group (“NTTG”) in accordance with FERC’s Order No.

328 1000. In fact, the current transmission system master plan for Wyoming calls for the
329 construction of facilities associated with Energy Gateway, specifically Energy Gateway
330 West and Energy Gateway South. The Aeolus-to-Bridger/Anticline line is a subset of
331 the Energy Gateway West project.

332 The Company has identified these projects in long-term transmission plans to:
333 (1) relieve congestion and increase transmission capacity across Wyoming, allowing
334 interconnection of new generation resources and enabling more efficient dispatch of
335 and greater flexibility in managing existing resources; (2) provide critical voltage
336 support to the transmission system; (3) improve system reliability; and (4) reduce
337 energy and capacity losses. As a part of the Combined Projects, however, customers
338 can economically obtain the much-needed support and benefits the Transmission
339 Projects will bring to the Company's existing transmission network.

340 **Q. Has any other party provided testimony addressing how the Transmission**
341 **Projects fit into the regional transmission plan?**

342 A. Yes. Mr. Davis specifically acknowledges that the NTTG has indicated that the
343 Wyoming transmission system requires "significant reinforcements" to "handle both
344 existing and future planned wind resources while maintaining all other Wyoming area
345 generating resources at their typical high capability in an export scenario." (Davis
346 Direct, lines 101-104.)

347 **Q. Mr. Mullins also claims the Company should invest in transmission projects that**
348 **improve reliability, rather than projects that are driven by economics. (Mullins**
349 **Direct, page 21, lines 7-10.) How do you respond to this claim?**

350 A. Mr. Mullins does not dispute the Company's extensive evidence that the Aeolus-to-

351 Bridger/Anticline Line will, in fact, improve reliability and relieve existing congestion
352 on the eastern Wyoming transmission system. Thus, by his own standards, the Aeolus-
353 to-Bridger/Anticline Line is the type of transmission investment that should be pursued.

354 **Q. Will the Transmission Projects also increase system efficiency?**

355 A. Yes. The addition of a transmission line together with an existing line or path will
356 reduce the impedance of the path, resulting in overall reduced energy line losses. Line
357 losses before and after construction of the Transmission Projects were compared, with
358 the difference being the line savings attributed to the Transmission Projects. Reduced
359 line losses mean more efficient delivery of energy and capacity at reduced costs with
360 or without the addition of new generation resources providing additional operational
361 flexibility of existing resources.

362 **Q. Have there been previous investments in transmission facilities along the TOT 4A**
363 **path?**

364 A. Yes. Since the time that the TOT 4A transmission path was initially defined, a
365 significant number of transmission additions and modifications have been made to the
366 Wyoming transmission system to increase the capacity on this path, including the
367 addition of new transmission lines (Spence-to-Mustang in 1991; Dave-Johnston-
368 Casper rebuild in 2010; and Sheridan-Dry-Fork-to-Hughes/Carr-Draw in 2010-11),
369 adding shunt capacitors for voltage support, implementation of dynamic line ratings
370 (Platte-to-Miners 230-kV line in 2013), and addition of a synchronous condenser (at
371 Standpipe in 2016).

372 As significant new facilities were added, WECC path-rating studies have been
373 performed to increase the rating of the path. The last set of path-rating studies were

374 completed April 17, 2013, with the granting of Phase 3 status by the WECC planning
375 coordination committee (“PCC”). These additions and subsequent path ratings have
376 supported the addition of resources behind the path to the point today where the
377 stiffness factor and the path rating cannot support additional resources without
378 infrastructure additions. Generation interconnection studies have shown that additional
379 resources cannot be reliably interconnected without the addition of transmission
380 infrastructure.

381 **Q. Mr. Hayet argues that the Company’s interconnection studies for the Wind**
382 **Projects assumed that additional Energy Gateway segments would be constructed**
383 **to facilitate interconnection of the Transmission Projects. (Hayet Direct, lines 743-**
384 **753.) How do you respond?**

385 A. The Company acknowledges that prior interconnection studies used Energy Gateway
386 “full-build-out” assumptions. The Company is currently revising applicable
387 interconnection studies to recognize that the Energy Gateway segments will be
388 constructed in phases.

389 **Q. Mr. Hayet also claims that the Combined Projects may not be the least-cost, least-**
390 **risk resources because the early retirement of the Dave Johnston plant may free**
391 **up sufficient transmission that another resource option is more economic than the**
392 **Combined Projects. (Hayet Direct, page 33, lines 679-695.) How do you respond?**

393 A. Mr. Hayet correctly testifies that retiring the 762 MW Dave Johnston plant will not, on
394 its own, obviate the need for the Aeolus-to-Bridger/Anticline transmission line because
395 the Dave Johnston plant provides critical voltage support to the 230-kV transmission
396 system and without that support, the Company could not integrate the Wind Projects

397 (or any other new resources). Mr. Hayet suggests, however, that early retirement,
398 coupled with some other solution to solve the voltage support issues, may be lower cost
399 than the Aeolus-to-Bridger/Anticline transmission line.

400 Based on feedback received during the 2017 IRP review process in
401 Oregon, the Company initiated transmission studies to provide additional clarity on
402 whether an early retirement of the Dave Johnston plant with the addition of new wind
403 resources could be a viable alternative to the Aeolus-to-Bridger/Anticline transmission
404 line. This analysis, which is being reviewed by an independent third-party, identified
405 that major reinforcement projects would be required on the 230 kV system to operate
406 the transmission system reliably and would eliminate the option of upgrading to 500
407 kV in the permitted rights of way. These studies indicate the reinforcement projects
408 would be more costly than the Aeolus-to-Bridger/Anticline line and result in less
409 incremental transfer capability out of eastern Wyoming.

410 **Q. Are there any other concerns associated with the early retirement of the Dave**
411 **Johnston plant?**

412 A. Yes. The Dave Johnston plant is one of the lowest variable-cost assets on the
413 Company's system and operationally, provides flexibility that facilitates the Company's
414 ability to import low-cost renewable energy from California through the energy
415 imbalance market (EIM). The plant also provides significant system capacity needed
416 to satisfy the Company's 13 percent target planning reserve margin and provides fault
417 current support to maintain "stiffness" of the grid which is necessary to support system
418 voltages. If Dave Johnston retired at the end of 2020 (approximately three years out),
419 there would be limited time to procure potential replacement resource alternatives

420 capable of delivering energy and capacity benefits comparable to those provided by the
421 Dave Johnston plant and could necessarily increase the Company's reliance on market
422 purchases. Retiring Dave Johnston by the end of 2020 would also create substantial
423 upward pressure on customer rates due to the accelerated depreciation resulting from
424 early retirement.

425 TRANSMISSION STUDY PROCESS

426 **Q. Mr. Peaco criticizes the Company's Preliminary Study Report. (Peaco Direct, lines**
427 **528-535.) What did that study conclude?**

428 A. The Preliminary Study Report concluded that the Transmission Projects will allow the
429 interconnection of the Wind Projects and increase the transfer capability from east to
430 west across Wyoming by 817.5 MW. In addition, the Preliminary Study Report
431 concluded that, with the addition of the Transmission Projects to the Wyoming
432 transmission system, the system performance will meet all NERC and WECC
433 performance criteria.

434 **Q. What concerns did Mr. Peaco raise?**

435 A. Mr. Peaco identified three concerns. First, Mr. Peaco claims that the assumptions and
436 methods used in the Preliminary Study Report are problematic. Second, Mr. Peaco
437 claims that the Preliminary Study Report does not support the Company's claim that
438 1,270 MW of new wind resources can be integrated. Third, Mr. Peaco claims that the
439 Preliminary Study Report is an initial report, and the actual WECC path transfer limit
440 will not be known until after construction begins.

441 **Q. Addressing Mr. Peaco's first concern, what assumptions does Mr. Peaco**
442 **challenge?**

443 A. Mr. Peaco argues that the Company assumed that multiple Remedial Action Schemes
444 (“RAS”) are necessary to resolve the reliability problem created by the integration of
445 large amounts of new wind generation. (Peaco Direct, lines 546-548.) Mr. Peaco claims
446 that planning on using RAS does not reflect prudent system operation.

447 **Q. How do you respond?**

448 A. A RAS is a tool recognized by NERC to protect the reliability and integrity of the Bulk
449 Electric System (“BES”). There are specific NERC standards in place to ensure that
450 RAS do not introduce unintentional or unacceptable reliability risks to the BES,
451 specifically PRC-012-2, which requires the RAS-entity to provide the RAS information
452 and documentation to the reliability coordinator before placing a new or functionally
453 modified RAS in service or retiring an existing RAS. The Company’s use of RAS for
454 generator tripping conforms to the NERC standards and is not imprudent or
455 unreasonable. It is important to note that the RAS the Company is proposing will not
456 trip load in the area. The RAS will be a generator tripping scheme that will take wind
457 resources offline only if a transmission facility outage condition occurs during periods
458 of high system transfers.

459 **Q. Mr. Peaco also claims that the Preliminary Study Report unreasonably relies on**
460 **the assumption that it is acceptable to severely limit the TOT 4B path to integrate**
461 **the new wind resources. (Peaco Direct, lines 556–558.) Please respond.**

462 A. Studies are ongoing for varying TOT 4B transfer levels, and it is not anticipated that
463 TOT 4B will be severely limited, or even limited at all. The Preliminary Study Report
464 is just one set of assumptions, and other flow levels will continue to be studied to

465 determine the full range of simultaneous operating interactions (nomograms) between
466 the TOT 4B and Aeolus West paths, just as with the TOT 4B and TOT 4A paths.

467 **Q. With respect to his second concern, Mr. Peaco argues that the customer benefits**
468 **of the Combined Projects would be eliminated if transmission limitations caused**
469 **even a relatively small reduction in the amount of wind resources that the**
470 **Company acquires. (Peaco Direct, lines 582–585.) Are you confident that the**
471 **Transmission Projects will allow the interconnection of the Wind Projects?**

472 A. Yes. Certain assumptions were made about the location of the proposed new wind
473 generation in the Preliminary Study Report, and these assumptions proved reasonable
474 based on the Wind Projects selected through the 2017R RFP. Based on this study and
475 ongoing study efforts, the Company has a high degree of confidence that it can
476 interconnect the amount of wind contemplated. Depending upon the ultimate size,
477 technology and location of new generation, interconnection of an even larger amount
478 of wind resources may be feasible.

479 **Q. Mr. Peaco claims that the Company’s use of dynamic line ratings for the Platte-**
480 **Standpipe 230-kV segment, rather than normal and emergency line ratings, was**
481 **improper. (Peaco Direct, lines 593–594.) How do you respond?**

482 A. I disagree that the Company’s use of dynamic line ratings was improper. If dynamic
483 line-rating devices are installed on a line, as they are on the Platte-Standpipe 230 kV
484 segment, the Company can properly exercise its engineering judgment to use dynamic
485 line ratings in planning studies. The Company monitored and studied conditions for
486 application of the dynamic line rating, (*i.e.*, ambient temperature, wind speed, etc.), in
487 real-time before for determining the appropriateness and implementation of the

488 dynamic line rating on the Platte-Standpipe 230-kV line. Dynamic line ratings have
489 been used in previous WECC path-rating reports, including the Comprehensive
490 Progress Report (“CPR”) for the TOT 4A (Path 37) and TOT 4B (Path 38) Path Rating
491 Increase Project, which was granted a Phase 3 rating by the WECC Planning
492 Coordination Committee (“PCC”) on April 17, 2013.

493 **Q. Mr. Peaco claims that the Preliminary Study Report improperly applied a**
494 **different assumption from the existing path definition by moving the Platte-area**
495 **load to the east of the Aeolus West cut-plane. (Peaco Direct, lines 603-604.) How**
496 **do you respond?**

497 A. This claim is incorrect. The definition of the Aeolus West path in the Preliminary Study
498 Report is consistent with that previously defined in the Energy Gateway West WECC
499 path-rating process.

500 **Q. Mr. Peaco claims that the Preliminary Study Report evaluated 1,169 MW of new**
501 **wind resources and therefore does not demonstrate that the Transmission Projects**
502 **will allow the interconnection of 1,270 MW of new wind resources. (Peaco Direct,**
503 **lines 625-627.) How do you respond?**

504 A. The Preliminary Study Report included a scenario with the addition of 1,270 MW of
505 wind as a sensitivity analysis, set forth in section 5 of the report. In addition, the final
506 shortlisted Wind Projects have a total capacity of 1,170 MW.

507 **Q. Mr. Peaco is also concerned that the assumptions used in the Preliminary Study**
508 **Report will not be accepted by WECC and that WECC’s path rating study will**
509 **not be completed until the Transmission Projects are under construction. (Peaco**
510 **Direct, lines 647-658.) Is this concern valid?**

511 A. No. At the March 30, 2010 Gateway West and Gateway South combined project review,
512 meeting participants approved the Gateway Phase 2 Study Plan and agreed that
513 incremental limitations for transmission segments added between states will be
514 addressed through System Operating Limit (“SOL”) studies. This same process was
515 previously followed and successfully demonstrated by the Bonneville Power
516 Administration and Avista for the West-of-Hatwai Expansion project. In addition to
517 SOL studies, which will be completed before the project goes into service, PacifiCorp
518 will be performing FAC-013-2 Transfer Capability Assessment studies, which it will
519 share with other utilities and WECC. These studies are scheduled for completion by
520 October 2019, more than one year before the project in-service date.

521 **RISK MITIGATION OF TRANSMISSION PROJECTS**

522 **Q. Mr. Hayet and Mr. Peaco are concerned that the Transmission Projects will not be**
523 **completed by the end of 2020 and may cost more than expected. (Hayet Direct,**
524 **lines 449-451; lines 470-485; Peaco Direct, lines 863-874; lines 956-958.) Mr.**
525 **Mullins also express a concern over the risk of cost overruns. (Mullins Direct, page**
526 **46, lines 13-17.) Please describe the Company’s experience mitigating these types**
527 **of transmission project risks.**

528 A. In the past five years, the Company has completed two significant and similar Energy
529 Gateway transmission projects: (1) the 100-mile 500/345-kV Mona-to-Oquirrh

530 transmission line; and (2) the 170-mile 345-kV Sigurd-to-Red-Butte transmission line.
 531 Similar to the Aeolus-to-Bridger/Anticline line, both projects required a NEPA-
 532 compliant environmental impact statement, including a record of decision, plan of
 533 development, and right-of-acquisition process. Using its expertise in utility resource
 534 development and project management, the Company delivered both the Mona-to-
 535 Oquirrh and Sigurd-to-Red-Butte transmission lines within the cost estimates used in
 536 the approval processes and on time. Table 2 below summarizes the actual project
 537 performance relative to the filing information:

538 **TABLE 2**

PROJECT	Original Filing Information				ACTUAL DATA	
	REF	Date of Application	COST (\$000,000s)	In Service	COST (\$000,000s)	In Service
Mona-Oquirrh	UT Docket 09-035-54	Nov. 21, 2009	\$ 450.00	5/31/2013	\$ 364.00	5/31/2013
Sigurd-Red-Butte	UT Docket 12-035-97	Sept. 17, 2012	\$ 380.00	6/30/2015	\$ 357.80	6/30/2015

539 The Transmission Projects have the same project-management team, and the Company
 540 developed the budget and schedule in the same manner as these earlier projects. The
 541 Company’s past experience substantially mitigates risks related to construction cost and
 542 schedule.

543 **Q. How confident are you in the cost estimates for the Aeolus-to-Bridger/Anticline**
 544 **Line?**

545 A. Very. The Company is confident that it will deliver the Aeolus-to-Bridger/Anticline
 546 Line at or below its cost estimates. Since starting the Energy Gateway program, which
 547 includes the Aeolus-to-Bridger/Anticline Line, the Company has used a Facilities
 548 Definition Document to clearly define and describe the required scope of the project to

549 all parties. The Facilities Definition Document is one of the foundations for the project
550 successes described earlier in my testimony. This document was updated before
551 developing the schedule and budgets that were included in the initial filing in this case.
552 A clear definition of the project scope from the beginning of the project life-cycle
553 brings an increased confidence in the accuracy of forecasts.

554 In addition, as an overall strategy of controlling contract cost and performance,
555 the Company will secure fixed-price, fixed-performance-date contracts that will
556 provide liquidated damages for late performance. The Company also uses project-
557 management techniques to trend and forecast performance, including earned-value
558 analysis, which provides an early notification of potential productivity concerns that
559 can then be addressed before becoming a major issue. In fact, the Company anticipates
560 executing contracts for the Aeolus-to-Bridger/Anticline Line (which is about 85 percent
561 of the overall Transmission Projects' cost) in early 2018 that will effectively lock-in the
562 cost for that line.

563 **Q. Mr. Mullins also claims that the Company's estimated incremental O&M costs for**
564 **the Transmission Projects is unsupported and the actual O&M may be much**
565 **higher. (Mullins Direct, page 46, lines 13-18.) How do you respond to this claim?**

566 A. The Company has a well-defined maintenance program that includes line and
567 substation inspections, preventative maintenance, and corrective maintenance. The
568 Company has extensive experience operating and maintaining both transmission and
569 distribution assets. Based on the defined maintenance programs and the Company's
570 experience with similar assets, the O&M costs assumed for this project are accurate.

571 **Q. Mr. Mullins further claims the Company has a history of under-estimating**
572 **transmission resource costs and cites the Populus-to-Terminal transmission line**
573 **as an example. (Mullins Direct, page 5, lines 11-15.) Is Mr. Mullins’s**
574 **characterization of the cost estimates for the Populus-to-Terminal line correct?**

575 A. No, Mr. Mullins’s testimony on this point is very misleading. Based on Company
576 filings in Idaho, Mr. Mullins testifies that the Populus-to-Terminal line was originally
577 estimated to cost \$78 million, but was actually constructed for \$801 million, implying
578 the Company’s estimate was understated by more than \$700 million. In fact, when the
579 Company requested a certificate of public convenience and necessity (“CPCN”) from
580 the Idaho Public Utilities Commission for the Populus-to-Terminal line, its cost
581 estimate was \$750 million, which was within seven percent of the final costs.³

582 **Q. What is the basis for Mr. Mullins’s claim that the Populus-to-Terminal line was**
583 **originally estimated to cost \$78 million?**

584 A. Mr. Mullins appears to have relied on a 2006 estimate provided by the Company in one
585 of its commitments stemming from the merger with MidAmerican Energy Holding
586 Company.⁴ Mr. Mullins’s testimony fails to note, however, that between the estimate
587 included in the merger commitment and the actual construction of the Populus-to-
588 Terminal line, conditions changed. Most notably, the 2006 merger commitment was a
589 high-level estimate of the cost to construct a 300-MW transmission line, while

³ See *In the Matter of the Application of Rocky Mountain Power For a Certificate of Public Convenience and Necessity Authorizing Construction of the Populus-to-Terminal 345 kV Transmission Line Project*, IPUC Case No. PAC-E-08-03, Order No. 30657 at 2 (Oct. 10, 2008).

⁴ *In the Matter of the Joint Application of MidAmerican Energy Holdings Company (MEHC) and PacifiCorp dba Utah Power & Light Company for an Order Authorizing MEHC to Acquire PacifiCorp*, IPUC Case No. PAC-E-05-08, Order No. 29998 at 6 (Mar. 14, 2006).

590 subsequent developments indicated that a much larger resource was required. The
591 Populus-to-Terminal line ultimately provided 700 MW of immediate additional
592 capacity and 1,400 MW of additional future capacity--a significant change from the
593 size contemplated in the merger commitment. Mr. Mullins's comparison of the \$78
594 million estimate in the merger commitment to the actual costs of the Populus-to-
595 Terminal line is inapt.

596 **Q. What about the risk of delay associated with obtaining the necessary permits and**
597 **rights-of-way for the Transmission Projects?**

598 A. The Company understands that the permitting process for transmission is complex, but
599 it is already well on its way to securing all required permits. In my testimony regarding
600 permit status, I note the Company is currently preparing applications for all of the major
601 remaining permits. The schedule anticipates completing the permitting process by the
602 end of 2018. To mitigate the risk of permitting delays, this schedule allows some delay
603 without adversely impacting the overall construction schedule.

604 In addition, to further mitigate the risk of potential delays, the Company is
605 actively engaging with stakeholders to inform them of the Transmission Projects and
606 the applicable permit application process. The Company meets with the BLM on a
607 regular basis to review project status, as well as planned or expected deliverables to the
608 BLM and cooperating agencies in relevant areas such as Section 106 consultation and
609 plan-of-development work. Similarly, the Company has met with the Wyoming ISC to
610 review the application process, and the Company will soon engage with agencies
611 supporting the Industrial Siting Permit to inform those agencies of the project details.
612 Engaging with stakeholders increases the ability to understand local needs, identify

613 appropriate approaches and potential mitigation, and successfully complete the permit
614 and approvals processes.

615 Although the Company does not intend to complete acquisition of rights-of-
616 way until early 2019, it is confident this timing will not delay the Transmission Projects.
617 The Company has engaged landowners on the projects since 2007 as part of its outreach
618 for the overall Energy Gateway West project. During that time the Company learned a
619 lot about the concerns of landowners and, where practical, has already addressed many
620 of them.

621 In summer 2017, the Company renewed discussions with all landowners about
622 the Transmission Projects. This effort identified, and continues to identify, additional
623 concerns and questions the Company is committed to resolve to balance the needs of
624 landowners with the project and its schedule. This renewed discussion will, through
625 previous experience, resolve many issues and lead to successful conclusion of
626 negotiations. Because any project will affect landowners in different ways, the effort
627 and timeframe for negotiations will vary from landowner to landowner. When
628 landowners are willing to actively engage in the process, timely resolution is almost
629 always assured.

630 **Q. How has the Company evaluated risks with the construction schedule?**

631 A. Project risks related to the construction schedule fall broadly into three classifications:
632 (1) restricted access due to environmental constraints; (2) weather restrictions; and (3)
633 late commencement due to late receipt of all permits.

634 To mitigate the potential impacts due to environmental constraints, the
635 Company considered its previous history constructing in areas with similar levels of

636 constraints and built the overall schedule based on this experience. From previous
637 practical experience and the ongoing agency engagements described in my testimony,
638 the Company understands that mitigation techniques, such as supervised or monitored
639 access into environmentally restricted areas, is possible through negotiation and
640 cooperation between parties. Additional mitigation plans, such as re-sequencing of
641 work or schedule compression, have also been successfully employed on previous
642 projects, with the contractor assuming the risk of occurrence for such items.

643 To mitigate the risk of constraints caused by weather, the schedule is set to
644 minimize construction during the winter and perform additional work in the summer.
645 In 2009, the Company engaged with several qualified and respected construction
646 contractors to analyze the feasibility of the construction program. This informed the
647 Company on the overall approach needed for the project and helped the Company
648 develop the project schedule. In addition, the Company is currently negotiating
649 contracts where the construction contractor will assume the risk for weather delays and
650 allow for such delays in their schedule and the guaranteed completion dates in the
651 contract.

652 **Q. What are the primary risks and mitigation measures underway?**

653 A. The primary risk in maintaining the critical-path construction schedule for the
654 Transmission Projects is the on-going regulatory review and approval processes
655 currently underway. Timely resource approval from the Commission is an important
656 element of managing the project schedule. The Company needs to obtain CPCNs from
657 the Wyoming Public Service Commission for the Transmission Projects, which are
658 conditioned upon acquisition of all necessary rights-of-way, with sufficient time to

659 meet this condition. The Company must also obtain the outstanding siting permits by
660 the end of 2018. If the Company does not receive conditional CPCNs in early 2018, or
661 siting permits by the end of 2018, it must assess the viability of achieving a year-end
662 2020 online date before moving forward. To manage the risk of obtaining timely
663 regulatory reviews and approvals, the Company will secure off-ramps in its EPC
664 contracts, allowing assurance of regulatory approvals before significant capital
665 commitments or outlays are made.

666 **Q. Is the Company confident that it can manage the construction-schedule risk and**
667 **deliver the Transmission Projects by 2020?**

668 A. Yes. To manage construction-schedule risk, the Company will structure and manage
669 the Transmission Projects on using firm, date-certain, fixed-price, turnkey contracts.
670 Construction contractors and equipment suppliers will be held to key construction and
671 delivery milestones and development of mitigation plans for compressed schedules, if
672 required. The Company will establish completion dates in the construction contracts
673 and backstop them with guarantees.

674 **Q. Does the Company have experience building similar types of projects that require**
675 **completion by a date-certain?**

676 A. Yes. The Company has managed multiple major projects that required the work be
677 completed by a date-certain, or similar circumstances where project completion was
678 required to allow a project to tie into an existing system within a short planned-outage
679 window or closely coordinated with delivery of transmission system network upgrades.
680 Examples of these projects include: (1) Dunlap wind facility; (2) High Plains wind
681 facility; (3) McFadden Ridge I wind facility; (4) Populus-to-Terminal 345-kV

682 transmission line; (5) Sigurd-to-Red-Butte transmission line; (6) Mona-to-Oquirrh
683 transmission line; (7) Lake Side 2 combined-cycle natural-gas facility; (8) Jim Bridger
684 Unit 3 and Jim Bridger Unit 4 selective catalytic reduction systems; (9) Naughton Unit
685 1 and Naughton Unit 2 flue gas desulfurization systems (“FDG”); (10) Hunter Unit 1,
686 Hunter Unit 2, Huntington Unit 1, and Huntington Unit 2 pulse jet fabric filters
687 (“PJFF”); (11) Wyodak PJFF; and (12) Dave Johnston Unit 3 and Dave Johnston Unit
688 4 PJFF and FGD systems.

689 **Q. If the Transmission Projects are not fully in service by December 31, 2020, can the**
690 **Wind Projects still qualify for PTCs?**

691 A. Yes. Assuming the Transmission Projects are not completed by December 31, 2020, but
692 otherwise have facilitated synchronization to the transmission grid and commissioning
693 of individual wind turbines in accordance with Internal Revenue Service (“IRS”)
694 guidance, the Company would treat a completed and functional wind turbine as being
695 placed in service regardless of any transmission constraints affecting a wind project.
696 Ms. Nikki Kobliha addresses this issue in her rebuttal testimony.

697 **Q. Mr. Davis claims that the Wind Projects may have to run at less than the full**
698 **capacity to allow room on the transmission system for thermal resources that**
699 **provide ancillary voltage and frequency service, and that this wind curtailment**
700 **will potentially limit PTC production. (Davis Direct, lines 265 - 282.) Please**
701 **respond.**

702 A. It is anticipated that system resources will be operated in the most efficient manner
703 feasible to maintain system integrity and reliability, which entails a combination of
704 wind and thermal resources. While Mr. Davis’ claim could technically be true at

705 times, particularly during a system event, this condition would be the exception rather
706 than the rule. Frequency response can be appropriately managed with relatively small
707 increases in thermal plant output. The Transmission Projects include plans for
708 dynamic voltage support, and the Company will finalize the design of these facilities
709 in summer 2018 now that the results of the 2017R RFP are available.

710 **COSTS ASSOCIATED WITH THE ENERGY IMBALANCE MARKET**

711 **Q. Mr. Mullins claims the EIM will impose additional costs on the Wind Projects**
712 **because they will be subject to uninstructed imbalance charges that were not**
713 **included in the Company's economic analysis. (Mullins Direct, page 43, lines 14-**
714 **17.) Is this true?**

715 A. No. There is no basis to assume that uninstructed imbalance will result in a net cost
716 and, in fact, the expectation is that over time there will be no net impact associated with
717 uninstructed imbalance.

718 **Q. What is uninstructed imbalance?**

719 A. Uninstructed imbalance in the EIM is assessed when a unit does not follow its
720 scheduled output in the five-minute market. For example, if the dispatch operating
721 target for five minutes was 50 MW and the unit actually produced 55 MW, then there
722 is an uninstructed imbalance of 5 MW. In this example, the 5 MW would be multiplied
723 by the locational marginal price of the unit to determine the uninstructed imbalance
724 assessment. Importantly, however, the assessment can be a charge or a credit because
725 the locational marginal price for a particular unit can be positive or negative. All of the
726 Company's generating units, as well as loads, have uninstructed imbalance. Mr.

727 Mullins is wrong to claim that uninstructed imbalance is somehow a negative outcome
728 that will impose additional costs.

729 Also, as described by Mr. Teply in his rebuttal testimony, the wind forecasts
730 that are provided to the Company's economic model are P50 forecasts, which assume
731 a balanced outcome over periods of times, *i.e.*, there is a 50-percent probability that
732 wind generation will be more than forecast and a 50-percent probability it will be below
733 forecast. To impute a negative pricing outcome assumes that the times when the unit is
734 under- or over-performing is somehow biased towards periods in which the dollar
735 impact is less favorable, *e.g.*, always under-performs when prices are high or over-
736 performs when prices are low (possibly negative). This would imply a bias in the
737 outcome, which is an unreasonable assumption in a forecast for variable energy
738 resources.

739 Finally, because the EIM is such a large, liquid market with renewable resource
740 diversity, it further supports the assumption of a balanced price outcome when a
741 resource or load deviates from a forecast.

742 **Q. Mr. Mullins also claims the EIM operates only on the ability to transfer power on**
743 **the firm rights of the Company, and does not allow transfers to occur on another**
744 **utilities' transmission rights. (Mullins Direct, page 43, lines 5-7.) Is this true?**

745 A. No. The opposite is true. The ability to use available transmission capability across the
746 Western Interconnect of participating EIM entities and the California Independent
747 System Operator Corporation ("CAISO") is the foundation of how benefits are realized
748 in the EIM.

749 **THIRD-PARTY TRANSMISSION REVENUE**

750 **Q. How will the costs of the Transmission Projects flow into the Company’s**
751 **transmission rates, and who will pay these rates?**

752 A. The Company’s current transmission formula rate (included in PacifiCorp’s OATT)
753 was approved by FERC in Docket No. ER11-3643. The Company’s transmission
754 formula rate is updated annually with the transmission revenue requirement (“ATRR”)
755 that represents the annual total cost of providing firm transmission service over the test
756 year. The ATRR calculation incorporates a return on rate base, income taxes, expenses,
757 and certain revenue credits, among other specific elements and adjustments.
758 Transmission assets, including new transmission capital, are included in the ATRR,
759 weighted by months in service. The ATRR is converted into a rate by dividing ATRR
760 by firm transmission demand. All third-party revenues for transmission service (along
761 with third-party revenues for ancillary services) are included as revenue credits in the
762 calculation of rates in each of the Company’s state retail jurisdictions.

763 **Q. Mr. Mullins and Mr. Peaco claim the Company has not supported its assumption**
764 **that 12 percent of the new investment in the Transmission Projects would be**
765 **funded by OATT customers. (Mullins Direct, page 45, lines 3-8; Peaco Direct, lines**
766 **1023-1024.) Is this true?**

767 A. No. As I explained above, FERC has approved the Company’s current formula rate that
768 will include the ATRR of the Transmission Projects once they are in-service, and the
769 Company has gone through the annual update. The 12 percent figure represents the
770 current level of ATRR funded by OATT customers.

771 **Q. Does this conclude your supplemental direct and rebuttal testimony?**

772 A. Yes.